



Car Park Refurbishment

PROJECT

TBC MSCP, Heathrow

CLIENT

British Airways

VALUE

£780,000.00

DURATION

20 Weeks (2 Phases)

PROJECT SPECIFICS

Following a detailed survey and concrete investigation, Matrix were engaged to carry out wide-scale concrete repairs and the application of coatings to this large reinforced concrete staff car park.

In conjunction with repairs to both soffits and decks, Duoguard sacrificial anodes and MN 15 reference electrodes were also buried within the structure to prevent future corrosion of the steel reinforcement and extract corrosion activity related data.

The large suspended main entry ramp into the car park was also waterproofed with a durable and fast cure membrane following removal of the existing worn coating, whilst Pavix CCC100 was applied to the decks of the concrete spiral exit ramp.

“Matrix were able to bring innovative solutions to the table which we felt added additional value over and above that of others”

- Client Engineer

If you want to know more about our Car Park Refurbishment please call [0845 230 1456](tel:0845 230 1456) or visit www.matrix.uk.com